CUT AND FILL ANALYSIS ROAD A WITH STORMWATER PONDS

Color	Range Beg.	Range End	Percent	Area
	22' CUT	15' CUT	2.0%	10,266 S.F.
	15' CUT	10' CUT	3.8%	20,086 S.F.
	10' CUT	5' CUT	9.5%	49,500 S.F.
	5' CUT	2' CUT	24.6%	128,672 S.F.
	2' CUT	2' FILL	47.1%	245,908 S.F.
	2' FILL	5' FILL	10.0%	52,205 S.F.
	5' FILL	10' FILL	3.1%	15,959 S.F.

LOTS 1–9 YIELD: 36,800± C.Y. CUT.
NOTE: GRADING OR CONSTRUCTION OF PAD SITES NOT INCLUDED.

LEGEND

- EXISTING MINOR CONTOUR
- EXISTING MAJOR CONTOUR
- EXISTING WETLAND
- PROPOSED EDGE OF ROAD WITH CURB
- PROPOSED SIDEWALK
- PROPOSED RIGHT OF WAY
- PROPOSED MINOR CONTOUR
- PROPOSED MAJOR CONTOUR

COPIES FROM THE ORIGINAL OF THIS DOCUMENT NOT MARKED WITH AN ORIGINAL OF THE PROFESSIONAL ENGINEER'S AND/OR LAND SURVEYOR'S STAMP OR EMBOSSED SEAL SHALL NOT BE CONSIDERED VALID, TRUE COPIES.

UNAUTHORIZED ALTERATION OR ADDITION TO THIS DOCUMENT IS A VIOLATION OF SECTION 7209-2 OF THE NEW YORK STATE EDUCATION LAW.

COPYRIGHT 2007, LANC & TULLY, P.C.

LANC & TULLY
ENGINEERING AND SURVEYING, P.C.
P.O. Box 687, Rt. 207
Goshen, N.Y. 10924
(845) 294-3700

CUT AND FILL ANALYSIS PLAN
PREPARED FOR
ROAD A AND STORMWATER PONDS

CORNWALL COMMONS

TOWN OF CORNWALL
ORANGE COUNTY, NEW YORK

Date: AUGUST 1, 2007
Revisions: AUGUST 29, 2007
CAD File: PHASING.DWG
Layout: CUT FILL RD A & PONDS
Sheet No.: 1 OF 1
Drawn By: JWC
Scale: 1" = 100'